

#### **Engineering & Operations Committee**

San Jacinto Diversion Structure Rehabilitation Slide Gate Procurement

Item 7-6 November 7, 2022 San Jacinto Diversion Structure

Slide Gate Procurement

#### **Current Action**

 Award a \$820,852.53 procurement contract to Whipps, Inc. for three slide gates to rehabilitate the San Jacinto Diversion Structure

## **Distribution System**




November 7, 2022

**Engineering & Operations Committee** 

Item # 7-6 Slide 3

## San Jacinto Diversion Structure


- Constructed in 1939
- Slide Gates V-01 & V-02
  - Controls flows into Casa Loma Siphon First Barrel
  - Supplies CRA water to Lake Mathews
- Slide Gate V-03
  - Controls flows into the San Jacinto Pipeline



## Background

- Slide Gate V-03 failed in 2019 & was removed
  - Temporary drop gate installed to provide isolation on San Jacinto Pipeline
- Significant corrosion identified on Slide Gates V-01 & V-02
  - Failure of Slide Gates V-01 or V-02 would impact operational control and flexibility

#### Slide Gate V-03



San Jacinto Diversion Structure

Slide Gate Procurement

### **Slide Gate Procurement & Installation**

- Slide gate fabrication & delivery expected to take up to 12 months
- Delivery scheduled for late-2023
- Slide gates to be installed during February/March 2024 CRA shutdown
- Operational by March 2024
- Installed under separate contract



Leakage Past Closed Slide Gates

## **Alternatives Considered**

- Rehabilitation
  - Replace components showing excessive wear
  - 10-year life span anticipated
  - Previously rehabilitated in 2011
- Selected alternative
  - Replace all three slide gates to avoid failure resulting in unplanned shutdown & operational impacts



Interior of San Jacinto Diversion Structure

San Jacinto Diversion Structure

Slide Gate Procurement

# Scope of Work

- Contractor
  - Furnish three slide gates
  - Deliver gates to Wadsworth Pumping Plant
- Metropolitan
  - Submittal review
  - Factory fabrication inspection
  - Off-load slide gates
  - Contract administration & project management

## Bid Results Specifications No. 2028

Bids ReceivedCNo. of Bidders3Lowest Responsible BidderVLowest Responsible Bid\$Range of other Bids\*\$Estimated Range of Costs\$

\* Two Non-Responsive Bids

October 6, 2022 3 Whipps, Inc. \$820,852.53 \$525,000 to \$720,000 \$500,000 to \$750,000

## Allocation of Funds

#### San Jacinto Slide Gates

#### Metropolitan Labor

Program mgmt., contract admin. & envir. support	\$ 62,000
Fabrication Inspection	79,000
Submittal review, technical support & record drwgs.	64,000
Force construction	5,000
Contract	
Whipps, Inc.	820,852.53
Remaining Budget	69,147.47
Total	\$1,100,000

# **Project Schedule**

San Jacinto Diversion Structure	2022	2023	2024
Procurement Final Design			
Preliminary Design Final Design	<ul> <li>Board Action</li> <li>Completion</li> </ul>		
Construction			

## **Board Options**

• Option #1

Award an \$820,852.53 procurement contract to Whipps, Inc. to furnish three slide gates and appurtenances to rehabilitate the San Jacinto Diversion Structure.

• Option #2

Do not proceed with this project at this time.

### Staff Recommendation

• Option #1

