

Engineering, Operations, & Technology Committee CRA Conveyance System Flow Monitoring Stations

Item 8-2 May 8, 2023

Current Action

 Award a \$5,266,000 contract to Leed Electric Inc. to install 12 flow monitoring stations along the Colorado River Aqueduct conveyance system

Project Location




Background

- Hydraulic capacity of CRA increased in 1990s by over 100 cfs
- Extended periods of 8-pump flow
 - Requires frequent monitoring & continuous maintenance
- Concerns & rationale for continuous monitoring
 - Pressurization of cut-and-cover conduits
 - Overflow of open sections



May 8, 2023



Cut-and-Cover Conduit Engineering, Operations, & Technology Committee



jging Engir Increased Water Elevation (Canal) Item # 8-2 Slide 4



Existing Monitoring Station

May 8, 2023

Scope of Work

- Installation of flow monitoring stations
- Provide real time data
- Continuously monitor & regulate flow
- Maintain steady state flow conditions

Alternatives Considered

- Install equipment in the open with shade canopies & an enclosed fence
 - Increased theft & vandalism in remote locations
- Selected Alternative Install equipment in pre-cast buildings
 - Provides comprehensive security & protection
 - Similar set-up to existing monitoring stations

Contractor - Scope of Work



Typical pre-cast concrete building

- Installation of pre-cast concrete buildings, antenna poles, & electrical ductbanks
- Site grading
- SCADA integration
- Rehabilitation of deteriorated
 accessways for conduits



Typical transducer installation in aqueduct Metropolitan - Scope of Work

- SCADA programming
- Providing access & coordinating clearances
- Construction management & inspection
- Submittal review
- Environmental monitoring
- Project management & project controls

Bid Results Specifications No. 2042

Bids Received No. of Bidders Lowest Bidder Low Bid Other Bid Engineer's Estimate SBE Participation* March 28, 2023 2 Leed Electric Inc. \$5,266,000 \$6,659,550 \$4,270,000 100%

* SBE (Small Business Enterprise) participation level set at 25%

Allocation of Funds

CRA Conveyance System Flow Monitoring Stations

Metropolitan Labor

Owner Costs (Proj. Mgmt., Contract Admin., Envir. Support)		\$ 466,000
Construction Inspection & Support		650,000
Submittals Review, Tech. Support, Record Dwgs.		387,000
Force Construction		180,000
Materials & Supplies		72,000
Professional/Technical Services		
Lee & Ro, Inc.		25,000
Construction Contract		
Leed Electric Inc.		5,266,000
Remaining Budget		704,000
	Total	\$7,750,000

Project Schedule



Board Options

- Option #1
 - Award a \$5,266,000 contract to Leed Electric Inc. to install 12 flow monitoring stations along the CRA conveyance system.
- Option #2
 - Do not proceed with the project at this time.

Staff Recommendation

• Option #1

