


# Engineering, Operations, & Technology Committee Colorado River Aqueduct Pumping Plants Storage Buildings

Item 8-2 June 12, 2023 Colorado River Aqueduct Equipment Storage Buildings

### **Current Action**

 Award a \$16,490,000 contract to J. F. Shea Construction Inc. to replace storage buildings at Hinds, Eagle Mountain, & Iron Mountain pumping plants

### **Project Location**



### Background

- Metal storage buildings built in 1950s
  - Decayed wooden frames
  - Metal walls & roof panels deteriorated
  - Limited storage capacity
- Gene Pumping Plant storage buildings were replaced in 2015
- Final design complete for replacement of storage buildings at Hinds, Eagle & Iron Mtn. pumping plants
  - Value engineering conducted to identify & implement cost saving measures for project



Iron Mtn. Storage Building (Existing)



Gene Storage Building (New)

Colorado River Aqueduct Equipment Storage Buildings

## **Alternatives Considered**

- Provide one large building instead of two
  - Limited space near pumping plants
  - Would increase retrieval time for parts
- Building types (tilt-up, masonry & steel)
  - Longer construction period
  - Costly materials
- Selected Alternative Replace single building with two pre-engineered buildings
  - Easier to site
  - Faster installation

#### Contractor – Scope of Work

- Demolish existing storage buildings
- Procure & install six pre-engineered metal storage buildings
- Grading for access & drainage improvements
- Construct concrete foundation pads, asphalt paving & fencing
- Install fire protection system new firewater lines & hydrants



Hinds Storage Buildings

Eagle Mtn. Storage Buildings

Iron Mtn. Storage Buildings

Engineering, Operations, & Technology Committee

### Bid Results Specifications No. 2000A\*

Bids Received No. of Bidders Lowest Responsible Bidder Low Bid Other Bid Engineer's Estimate SBE Participation\*\* April 20, 2023 2 J. F. Shea Construction Inc. \$16,490,000 \$19,668,656 \$17,460,000 33%

\* This contract will be conducted under the terms of Metropolitan's project labor agreement
\*\* SBE (Small Business Enterprise) participation level set at 25%

# **Comparison of Recent Storage Building Projects**

- Cost Analysis Findings CRA Storage Buildings
- 6 buildings across 3 separate facilities
- Extensive site work required for CRA buildings
  - Extensive site grading & erosion control
  - Electrical & water source farther from new buildings
  - Fire protection systems & hydrants needed for 3 separate buildings
  - Environmental fencing
- Demolition of existing buildings
- Remote Desert locations

Contract Cost Comparison	CRA Storage Buildings (2023)	Lake Mathews Storage Building (2021)	
Contract cost	\$16,490,000	\$4,759,000	
Sitework & demo. cost	\$8,436,000	\$2,075,000	
Building cost	\$8,054,000	\$2,684,000	
Total building area, sq. ft.	27,660	18,200	
\$ per sq. ft.	\$291	\$147	

Colorado River Aqueduct Equipment Storage Buildings

### Metropolitan - Scope of Work

- Integration of fire alarm system with SCADA
- Installation of ventilation exhaust fans
- Construction management & inspection
- Submittals review & preparation of record drawings
- Environmental monitoring
- Project management, project labor agreement administration & project controls

### **Allocation of Funds**

CRA Storage Buildings at Hinds, Eagle Mtn. & Iron Mtn. Metropolitan Labor Owners Costs (Proj. Mgmt., Contract Admin., Envir. Support) \$ 680,000 **Construction Inspection & Support** 1,830,000 128,000 Force Construction Submittals Review, Tech. Support, Record Dwgs. 617,000 Materials & Incidentals 31,000 Contracts J. F. Shea Construction Inc. 16,490,000 1,024,000 Remaining Budget Total

20.800.000

## **Project Schedule**

Project	2023	2024	2025	
CRA Storage Buildings at Hinds, Eagle Mtn. & Iron Mtn.				
Construction		Board Action		
	Completion			

### **Board Options**

• Option #1

Award a \$16,490,000 contract to J. F. Shea Construction Inc. for furnishing and installation of pre-engineered storage buildings at the Hinds, Eagle Mountain, and Iron Mountain pumping plants.

• Option #2

Do not proceed with the project at this time.

### **Staff Recommendation**

• Option #1

