

Engineering, Operations, & Technology Committee

Allen-McColloch Pipeline Urgent PCCP Rehabilitation Stage 2

Item 8-1 May 13, 2024

Item 8-1 Allen-McColloch Pipeline Urgent PCCP Rehab Stage 2

Subject

Award a \$24,912,000 construction contract to J.F. Shea Construction Inc. for urgent rehabilitation of prestressed concrete cylinder pipe portions of the Allen-McColloch Pipeline; authorize an increase of \$250,000 to an agreement with Helix Environmental Planning Inc. for a new not-to-exceed amount of \$2,500,000; and authorize an amendment to Metropolitan's Project Labor Agreement to add the subject project to the list of covered projects

Purpose


This action rehabilitates approximately 2.4 miles of the Allen-McColloch Pipeline (AMP)

Recommendation and Fiscal Impact

Award a construction contract for the PCCP rehabilitation of the AMP and authorize an increase to an agreement for environmental support Fiscal Impact of \$31.9 million


Budgeted

Location Map




AMP Urgent PCCP Rehab Recap

- Steel (Apr '24)
- CFRP (Apr '24)
- Steel (in progress)



AMP Stage 1 overview










AMP Urgent PCCP Rehab - Stage 2 Alternatives



Distressed segments – Stage 2

Initial Option

Rehabilitate only distressed pipe segments

- Focus on 18 pipe segments with 20 to 130 wire breaks
- Does not address shorter than expected service life of AMP PCCP

Selected Option


Complete steel relining of all PCCP downstream of OC-88

- Approach selected after consultation with MWDOC
- Efficient and cost-effective
- Minimizes service interruptions and reduces risks of PCCP failure

AMP Urgent PCCP Rehab. - Stage 2 Scope of Work

Reline 12,700 ft of PCCP:

- Temp. traffic controls
- Temp. portals (11)
- Installation, welding & grouting of new liner
- Backfill & compaction
- Restoration of streets& disturbed areas



AMP Urgent PCCP Rehabilitation Stage 2

Metropolitan Scope of Work

- Shutdown & return to service
- Construction management & inspection
- Contract administration, engineering support
- Environmental monitoring, public outreach & project management





Bid Results Specifications No. 2108*

Bids Received April 12, 2024

No. of Bidders

Lowest Responsible Bidder J.F. Shea Construction Inc.

Low Bid \$24,912,000

Other Bid \$34,407,000

Engineer's Estimate \$25,800,000

SBE Participation** 14%

^{*}Contract included in PLA

^{**}SBE (Small Business Enterprise) participation level set at 5%

AMP Urgent PCCP Rehabilitation Stage 2

Helix Environmental Planning Inc. – Agreement Amendment

- Selected via RFP No. 1157
- Perform monitoring during construction
- Prepare environmental documentation to comply with environmental regulations
- Increase of \$250,000 for a new NTE amount of \$2.5 M

Allocation of Funds

Allen-McColloch Pipeline Urgent PCCP Rehabilitation – Stage 2

Metropolitan Labor

Owner Costs (Proj. Mgmt., Contract Admin., Envir. Supp	ort) \$ 669,000
Construction Inspection & Support	2,518,000
Force Construction	1,438,000
Submittals Review, Tech. Support, Record Dwgs.	770,000
Materials & Incidentals	162,000
Professional/Technical Services	449,000
Right-of-Way	149,000
Contracts	
J.F. Shea Construction Inc.	24,912,000
Remaining Budget	833,000
	Total \$ 31 000 000

Total \$ 31,900,000

Project Schedule



Board Options

- Option #1
 - a. Award a \$24,912,000 contract to J.F. Shea Construction Inc. to rehabilitate approximately 2.4 miles of PCCP portions of the Allen-McColloch Pipeline.
 - b. Authorize an increase of \$250,000 to an agreement with Helix Environmental Planning Inc. for a new not-to-exceed amount of \$2,500,000.
 - c. Amend Metropolitan's Project Labor Agreement to include the Allen-McColloch Urgent PCCP Rehabilitation Stage 2 Project.
- Option #2

Do not award a construction contract to rehabilitate the AMP and do not amend an agreement for environmental planning support at this time.

Staff Recommendation

Option #1

